

25.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T16N R 34W	F9
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S28 T16N R 34W	16
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

F9 Jul 28 1998
16 Jul 29 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(F9) Quarter corner coason to Sections 21-28. Corner established in 1852 by Zelotes B. Searles: "...39.935 Set quarter Section Post.
B. Ash B S50W 35, do B N31E 37." Found no subsequent record.
(16-Sec. 28) East 1/16 corner between Sections 28-33. Corner was not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F9) Original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. I reestablished this corner midway and on a line of mean true bearing between Section corners 39.9725 ch. East and West. At the position for the corner I placed a 1" I.D. x 32" iron pipe capped with a yellow plastic cap stamped "MICH DNR PS 33986". Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.
(16-Sec. 28) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a line of mean true bearing between quarter corner 19.9233 ch. west and Section corner 19.9233 ch. east. At the position for the corner I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F9) Set 1" pipe with yellow plastic cap. Blazed and scribed the following:	(16) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following:
9" B. Ash N55W 4.1' 1/4S NBT	11" Hemlock N09E 15.5' 1/16S BT
12" Cedar N28E 39.4' do	14" Y. Birch S16W 55.0' do
14" B. Ash N66E 15.45' do	12" Cedar S56W 58.8' do
6" Y. Birch S24E 61.5' do	10" Hemlock N52W 17.5' do
Placed a squared cedar post adjacent.	Placed a squared maple post adjacent.
Distances are to meas. notch. Bearings are magnetic.	Distances are to meas. notch. Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 12/29/98

For the Michigan Department of Natural Resources - Forest Management Division