

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T16N R 34W	111
	T _____	_____
	T _____	_____
2. Property Controlling in Section	S _____	_____
	S _____	_____
3. Miscellaneous Property in Sec.	S _____	_____
	S _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Jul 28 1998

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:  
(I11) Corner common to Sections 26-27-34-35. Corner established in 1852 by Zelotes B. Searles: "N3'E Corrected...80.24 Set post Cor. of Secs. 26, 27, 34 & 35. W. Pine 28 S50E 1, Cedar 10 N50W 9." Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I11) Original post was not recovered. Remonumented the corner at the position of a very old squared post bottom, rotted off at ground level, with the post laying on the ground, adjacent. The post was recovered at record bearing and distance from what appears to be the rotted stump remains of the original W. Pine BT. There are several marked trees nearby: an 11" Spruce N65W 5.9' blazed 8H and below and scribed "S27 BT", an 11" Spruce S07E 34.2' blazed 8H and below and scribed "S35 BT", and a blazed 11" Balsam N51E 2.5 with single blaze with 2 sets of "ears". According to growth ring count the Spruce S07E was marked about 42 years ago. The original cedar BT NW was not recovered. Original GLO corners were found 40.0072 ch. west (40.06R) and 40.0728 ch. east (40.12R). I accept the post bottom as the best available evidence of the position of the original corner. At the position for the corner I placed a 1"IDx32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I11) Set 1" pipe with 4" MDNR cap.  
Blazed and scribed the following:  
12" Spruce N18W 27.4' "S27 NBT"  
12" Spruce N14E 48.25' "S26 NBT"  
15" Spruce S87E 40.45' "S35 NBT"  
12" Spruce S24W 50.05' "S34 NBT"  
Distances are to meas. notch. Bearings are magnetic.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 12/29/98

For the Michigan Department of Natural Resources - Forest Management Division