

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron (County)	Located in:	Corner Code #
1. Public Land Survey	T46N R 34W	G11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S22 T46N R 34W	10
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

10 Jul 27 1998  
G11 Jul 21 1998

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(G11) Corner common to Sections 27-28-33-34. Corner established in 1852 by Zelotes B. Searles: "N8°W Corrected...79.90 Set post Cor. of Secs. 27, 28, 33 & 34. Heal 12 S60E 14, Y. Birch 22 N22W 30." Found no subsequent record.  
(10-Sec. 22) South 1/16 corner between Sections 21-22. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G11) Original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner by double proportionate measurement to the original record between original corners 39.8467 ch. west (39.815R), 79.8905 ch. north (79.90R), 40.0876 ch. east (40.06R), and a corner restored from local evidence 79.8905 ch. south (79.90R). At the position for the corner I placed a 1" IDx32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.  
(10-Sec. 22) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a line of mean true bearing between Section corner 20.0447 ch. South and Quarter corner 20.0447 ch. North. At the position for the corner I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office. I found a 5/8" dia. rebar 6' long, driven to project 48", S69E 5.1' from the corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G11) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following: 7" Y. Birch S55W 5.4'    "S33 NBT" 16" Y. Birch N21W 46.95'    "S28 NBT" 6" Y. Birch N27E 27.9'    "S27 NBT" 16" Hemlock S80E 40.65'    "S34 NBT" Placed a squared sugar post adjacent. Distances are to meas. notch. Bearings are magnetic.	(10) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following: 12" Cedar S81E 10.6'    "1/16S BT" 7" Y. Birch S10W 25.4'    do 7" Y. Birch S57W 25.1'    do 15" Hemlock N11E 46.5'    do Placed a squared cedar post adjacent. Distances are to meas. notch. Bearings are magnetic.
--	---



Signed by Stephan J. Szyszkoski Date 12/29/98  
Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division