

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

29.

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T46N R 34W	H10
	T46N R 34W	I10
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I10 Jul 28 1998
H10 Aug 03 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
(H10) Center of Section 27. Corner not established in the original survey. Found no subsequent record.
(I10) Quarter corner common to Sections 26-27. Corner established in 1852 by Zelotes B. Searles; "N3'E Corrected...40.12 Set quarter Section post. Sugar B N70E 15, Fir 4 N47W 17." Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H10) Found no evidence of prior monumentation at the corner position. Established the corner at the intersection of straight lines connecting opposite quarter corners. At the position for the corner I placed a 1"IDx32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.
(I10) Original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner midway and on a line of mean true bearing between Section corners 40.0646 ch. north and south. I observed the true bearing of the line to be N 8° 11' E. I found an old squared post, down on the ground, apparently an approximate corner position, roughly S80E 42 ft. from the corner position. At the position for the corner I placed a 1"IDx32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H10) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following: 9" Y. Birch N20W 9.4' C1/4 8T' 10" Y. Birch S47E 9.0' do 15" Y. Birch S71W 26.2'(slope) do 9" Y. Birch N46E 35.9'(slope) do Placed a squared sugar post adjacent. Distances are to meas. notch. Bearings are magnetic.	(I10) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following: 10" Y. Birch S18E 14.75' "1/4S NBT" 12" Y. Birch N23E 24.0' do 10" Sugar N49W 31.85' do 9" Sugar S28W 32.55' do Placed a squared maple post adjacent. Distances are to meas. notch. Bearings are magnetic.
---	---



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 12/29/98

For the Michigan Department of Natural Resources - Forest Management Division