

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>34W</u>	<u>67</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Aug 04 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(G7) Corner common to Sections 15-16-21-22. Corner established in 1852 by Zelotes B. Searles: "N89 deg. 50'E corrected...80.00 Set post Cor. of Secs. 15,16,21,22. Y. Birch 12 S42E 5, Fir 10 N78W 27."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G7) Original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner by double proportionate measurement to the original record between probable original corners 39.9425 ch. West (40.00 Rec.), 120.2488 ch. North (120.00 Rec.), 40.0336 South (39.95 Rec.), and 68.5065 ch. East (MC 68.60 Rec.). At the position for the corner I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. From the corner, swamp calls west and top of ridge north check well with the original record. Swamp calls south and east check approximately. I recovered an old fence post N32E 44' from the corner. Corner placed and witnessed by D.Laapela and B.Wheeler, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G7) Set a 1" pipe with 4" MDNR cap.

Blazed and scribed the following:

10" Cedar S85W 39.45' "S21 NBT"

8" Maple N43W 33.5' "S16 NBT"

12" Y. Birch N53E 61.8' "S15 NBT"

18" Y. Birch S16E 16.15' "S22 NBT"

Placed a squared cedar post adjacent.

Distances are to meas. notch. Bearings

are magnetic.



Signed by

Stephan J. Szyszkoski

Surveyor's Michigan License No.

33986

Date

12/29/98

For the Michigan Department of Natural Resources - Forest Management Division