

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>34W</u>	<u>H9</u>
	T <u>46N</u> R <u>34W</u>	<u>E10</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

E10 Jul 23 1998

H9 Jul 22 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5						3		2			1
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(H9) Quarter corner common to Sections 22-27. Corner established in 1852 by Zelotes B. Searles: "...39.98 Set quarter Sec. post. Fir 8 S55E 38, do 10 N40W 26." Found no subsequent record.

(E10) Quarter corner common to Sections 28-29. Corner established in 1852 by Zelotes B. Searles: "N5'E Corrected...39.99 Set quarter Section post. Fir 10 S16W 21, Maple 14 N40E 22." Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H9) Original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner midway and on a line of mean true bearing between Sections corners 40.0201 ch. east and west. At the position for the corner I placed a 1"IDx32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. There is a 19" spruce, squared, in the corner area, which has seemingly been used for an approximate corner. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.

(E10) Original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner midway and on a line of mean true bearing between Section corners 40.0392 ch North and South. The bearing of this line was observed to be N 8' 31" W. At the position for the corner I placed a 1"IDx32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H9) Set 1" pipe with 4" MDNR cap.
 Blazed and scribed the following:
 17" W. Spruce S20E 8.2' 1/4S NBT"
 14" Cedar S45W 48.0' do
 8" Sugar N86W 20.0' do
 5" Sugar N03W 4.8' do
 Placed a squared sugar post adjacent.
 Distances are to meas. notch. Bearings
 are magnetic.

(E10) Set 1" pipe with 4" MDNR cap.
 Blazed and scribed the following:
 16" Cedar S43W 25.55' 1/4S NBT"
 14" Cedar S82W 17.8' do
 8" Sugar N57E 40.3' do
 22" Hemlock S72E 71.35' do
 Distances are to meas. notch. Bearings
 are magnetic. Squared an 8" Maple N67W
 1.3' to tree center.



Signed by

Stephan J. Szyszkoski
 33986

Surveyor's Michigan License No.

Date

12/29/98

For the Michigan Department of Natural Resources - Forest Management Division