

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>46N</u> R <u>34W</u>	<u>68</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S <u>27</u> T <u>46N</u> R <u>34W</u>	<u>1</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1 Jul 22 1998
68 Jul 14 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(68) Quarter corner common to Sections 21-22. Corner established in 1852 by Zelotes B. Searles: "NOB'N Corrected...39.95 Set quarter Section post. Y. Birch 12 S30E 13, do 8 N52W 22." Found no subsequent record.
(1-Sec. 27) West 1/16 corner between 22-27. Corner not established in the original survey. Found no subsequent record.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(68) Original post was not recovered. Restored the corner from the probable remains of the Y. Birch BT MN, now a decayed hollow stump 20" dia. with a deep scar on the SE face. The 2nd BT Y. Birch was not recovered. To the NW, a squared corner on a 12" Hemlock with a Celotex location poster attached points to this location. Also, a squared corner on a 20" Hemlock bearing S77W 6.2' points to this location. A probable original corner is S09'W 40.0893 ch. South (39.95 ch. rec) and a reestablished Section corner is N23'W 40.0335 ch. (39.95 ch. rec). At the position for the corner I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.
(1-Sec. 27) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a line of mean true bearing between Section corner 20.0099 ch. west and Quarter corner 20.0099 ch. east. At the position for the corner I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office. Found Celotex and American Can Co. posters nearby for approximate corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(68) Set 1" pipe with 4" MDNR cap.
Blazed and scribed the following:
12" Hemlock N22W 23.95' 1/4S NBT"
6" Sugar N66E 6.15' do
7" Y. Birch S38E 17.55' do
20" Hemlock S75W 6.25' do
Placed a squared cedar post adjacent.
Distances are to meas. notch. Bearings are magnetic.

(1) Set 1" pipe with 4" MDNR cap.
Blazed and scribed the following:
8" Sugar N52E 18.0' 1/16S BT"
8" Sugar S04E 20.1' do
10" Sugar S49W 20.6' do
12" Y. Birch N40W 43.5' do
Placed a squared sugar post adjacent.
Distances are to meas. notch. Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 12/29/98

For the Michigan Department of Natural Resources - Forest Management Division