

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|---------------------------------------|-------------------------|---------------|
| Iron | Located In: | Corner Code # |
| (County) | | |
| 1. Public Land Survey | T 46N R 34W | 1B |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling In Section | S 19 T 46N R 34W | 10 |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1B Aug 05 1998
10 Aug 18 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

(1B) Quarter corner common to Sections 22-23. Corner established in 1852 by Zelotes B. Searles: "40.12 Set quarter section post. Cedar 12 S85W 8, do 12 East 7." December 1953 record of Northern Paper Mills at Mad Lake Timber and Land Co. state: "1930: Cole and Sillers found 12" ced. B.T. East dead. 1953: Mickaan and Peryan found post 12" Ced. E old face no I.M. Set pipe at post from Cedar. Description of corner monument: Iron pipe and brass cap. Witnesses to corner Ced. 10 S4W 14." Found no subsequent record.
(10-Sec. 19) South 1/16 corner between Section 19 T46N-R34W and Section 24 T46N-R35W. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(1B) Recovered the 1953 monument as described, a 1" ID iron pipe capped with a 2" brass Northern Paper Mills tablet, appropriately stamped, in good condition, and at record bearing and distance from the 1953 witness cedar, found in good condition. Scribing is visible on both upper and lower blazes. I accept the monument as a careful and faithful perpetuation of the position of the original corner. Left the monument in place and marked three new accessories as described below. Corner recovered and remitted by D.Lampela and B.Wheeler, Baraga District Office.
(10-Sec. 19) Found no evidence of prior monumentation at the corner position. Established the corner on a line of mean true bearing between Section corner 19.9572 ch. South and Quarter corner 19.9572 ch. North. At the position for the corner I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| (1B) Found 1" pipe with brass MPH cap. Blazed and scribed the following: 12" Cedar N55E 31.4' "1/4S NBT" 5" Tamarack S77E 19.1' do 6" Tamarack N85W 7.1' do The 1953 witness: 11" Cedar S01W 9.1' marks visible. Placed a squared cedar post north 1'. Distances are to meas. notch. Bearings are magnetic. | (10) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following: 8" Y. Birch N05E 25.5' "1/16S BT" 20" Hemlock N02E 39.2' do 22" Sugar S42E 3.0' do 8" Hemlock N68W 25.4' do Placed a squared cedar post adjacent. Distances are to meas. notch. Bearings are magnetic. |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 12/29/98

For the Michigan Department of Natural Resources - Forest Management Division