

36.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 46N R 34W	87
	T 46N R 34W	C7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

C7 Jun 25 1998
87 Aug 11 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7	●	●											
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(B7) Quarter corner common to Sections 18-19. Established in 1852 by Zelotes B. Searles: "N89 deg. 50'E Corrected... 38.50 Set quarter post. Spruce 8 S30W 15, Tan 10 N70E 29...78.50 Set post Cor. Secs. 17,18,19,20." Found no subsequent record.
(C7) Corner common to Sections 17-18-19-20. Corner restored in 1986 by Keith L. Sackett RLS 19006: "Found old post set by unknown person. Restored at old post. Position fits good with other corner and land calls. Set 1" ID by 32" IP with 4" alum. cap. 8" Cedar S84W 85.3', 5" Maple S32W 42.1', 8" Maple S13E 66.2'."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B7) Original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner on a line of mean true bearing between Section corners 40.2758 ch. east and 38.7655 ch. west, being proportionate to the original record. At the position for the corner, I placed a 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.
(C7) Recovered the 1986 monument as described, a 1" ID iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped, in good condition, and at record bearing and distance from the Maple SW and Cedar SW bearing trees, both in good condition. Left the monument in place and marked three new accessories as described below. Corner recovered and re-witnessed by D.Lampela and B.Wheeler, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B7) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following: 10" Cedar N18E 38.25' "1/4S NBT" 9" twin Cedar S02W 29.0' do (the 9" Cedar leans heavily east) 13" Cedar S61W 64.15' "1/4S NBT" 12" Tamarack N52W 31.6' do Placed a squared cedar post adjacent. Bearings are magnetic. Distances are to meas. notch.	(C7) Found 1" pipe with 4" MDNR cap. Blazed and scribed the following: 8" W. Spruce N11E 63.7' "S17 NBT" 4" Twin W. Birch S37W 16.7' "S19 NBT" 11" W. Spruce S73W 62.7' "S19 NBT" Bearings are magnetic. Distances are to meas. notch.
--	---



Signed by

Stephan J. Szyszkoski
33986

Date

12/29/98

Surveyor's Michigan License No.

For the Michigan Department of Natural Resources - Forest Management Division