

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

39.

For corners in

Iron _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T 46N R 34W	E12
	T 46N R 34W	E6
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

E6 Aug 10 1998
E12 Jul 13 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													


A. Description of original monument and accessories and/or subsequent restoration:
(E12) Quarter corner common to Sections 32-33. Corner established in 1852 by Zelotes B. Searles: "N5'E Corrected...39.99 Set quarter Section post. Y. Birch 22 S5W 23, Heal 12 N82E B." Found no subsequent record.
(E6) Quarter corner common to Sections 16-17. Established in 1852 by Zelotes B. Searles: "40.00 Set quarter Section post. fir 4 S23E B, do 3 N35W 20." Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E12) Original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner midway and on a line of mean true bearing between Section corners 40.0480 ch. north and south. I observed the true bearing of this line to be N18°19'E. At the position for the corner I placed a 1"IDx32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.
(E6) Original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner midway and on a line of mean true bearing between Section corners 39.831 chains north and south. At the position for the corner, I placed a 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E12) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following: 8" Sugar N79E 35.1' "1/4S N8T" 15" Maple S22W 9.2' do 14" twin Hemlocks S67W 36.3' do 15" Sugar N39W 5.4' do Placed squared sugar post adjacent. Distances are to meas. notch. Bearings are magnetic.	(E6) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following: 14" W. Spruce S60E 17.0' "1/4S N8T" 8" Twin Maple S47E 20.9' do 7" Maple S41W 10.3' do 8" W. Spruce N56W 47.7' do Placed a squared spruce post adjacent. Bearings are magnetic. Distances are to meas. notch.
---	---



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 12/29/98

For the Michigan Department of Natural Resources - Forest Management Division