

42.

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 46N R 34W	AB
	T 46N R 34W	G6
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

G6 Aug 04 1998  
AB Aug 13 1998

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

(AB) Quarter corner common to Section 19, T46N-R34W and Section 24 T46N-R35W. Corner established in 1846 by Wm. A. Burt: "North... 40.00 Set Y. Birch Post Qr. Sec. Cor. on North side of hill. Fir 12 S55E S, Healock 18 N50W 11." Cruiser notes dated 1/24/1934 on file with the USFS Surveyor at Ironwood, MI are not clear but seem to state: "Fd. Cedar stake good condition with scribing [unclear whether scribing is on post or a tree]. Post is 5 ft. south of 7" cedar. Believe GLO". Found no subsequent record.  
(G6) Quarter corner common to Sections 15-16. Established in 1852 by Zelotes B. Searles: "40.00 Spt quarter Section post. Cedar 14 S40E 28, do 12 N23W 28." Found no subsequent record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(AB) Original post and accessories were not recovered. Cedar and stake noted in the 1934 cruiser report were not recovered. Found no acceptable evidence of the position of the original corner on the ground. I reestablished the corner on a line of mean true bearing between Section corners 39.9143 chains north and south (40.00 ch. GLO). I observed the bearing along this line to be only 3 arc-seconds west of true north. At the position for the corner I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.  
(G6) Original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner midway and on a line of mean true bearing between Section corners 40.083 chains north and south, being proportionate to the original record. At the position for the corner, I placed a 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(AB) Set 1" pipe with 4" MDNR cap.	(G6) Set 1" pipe with 4" MDNR cap.
Blazed and scribed the following:	Blazed and scribed the following:
14" Y. Birch N07E 42.0' * "1/4S MBT"	10" Cedar N65E 17.85' "1/4S MBT"
17" Healock S22E 17.8' do	10" Cedar S01W 35.6' do
10" W. Spruce S08W 44.3' * do	13" Cedar N84W 46.55' do
16" Y. Birch N49W 20.0' * do	10" Cedar N23W 37.1' do
Placed a squared cedar post adjacent.	Placed a squared cedar post adjacent.
Distances are to meas. notch. Bearings are magnetic. Dist. noted with * are measured along the slope.	Bearings are magnetic. Distances are to meas. notch.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 12/29/98

For the Michigan Department of Natural Resources - Forest Management Division