

46.

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

|                                       |             |               |
|---------------------------------------|-------------|---------------|
| Iron<br><small>(County)</small>       | Located In: | Corner Code # |
| 1. Public Land Survey                 | T 46N R 34W | A9            |
|                                       | T R         |               |
|                                       | T R         |               |
|                                       | T R         |               |
| 2. Property Controlling<br>in Section | S T R       |               |
|                                       | S T R       |               |
| 3. Miscellaneous<br>Property in Sec.  | S T R       |               |
|                                       | S T R       |               |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Aug 18 1998

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    |    |    |    |    |    |    |   |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
| 1  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

**A. Description of original monument and accessories and/or subsequent restoration:**

(A9) Corner common to Sections 19-30 T46N-R34W and 24-25 T46N-R35W. Corner established in 1846 by Wm. A. Burt: "North... 80.00 Set maple post cor. of secs. 24 and 25. Lynn 18 N72E 22, Hemlock 20 N72W 25." Further BT by Z.B. Searles in 1851: Y. Birch 10 S31E 23. Cruiser notes dated Jan. 20, 1934 on file at the office of the USFS Surveyor in Ironwood show: "Hemlock good condition 7' above ground (?) no iron marks. Tag on S. side of tree. Blazes and markings on tree by LES. Clarence Jones 1/20/34"

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(A9) Original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Near the corner position, I found two blazed and painted Hemlocks and a triple 19" basswood with a very old Forest Service location poster attached. Painted blue lines run North and East from one of the Hemlocks, which bears N52E 34.5' from the position subsequently monumented. The blazes date back to around 1958, by count of the growth rings. I reestablish the corner by single proportionate measurement to the original record, on a line of mean true bearing between USFS monument for Quarter corner 39.9146 ch. South and USFS monument for Section Corner 79.8287 ch. North. I observed the bearing of this line to be 4 arc-seconds West of true North. At the position for the corner I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(A9) Set 1" pipe with 4" MDNR cap.  
Blazed and scribed the following:  
10' Hemlock N52E 34.5'(slope) S19 NBT"  
10' Y. Birch S45E 10.2' S30 NBT"  
20' Hemlock S08W 33.3' S25 NBT"  
10' Y. Birch N16W 3.2' S24 NBT"  
The 20' Heml. has an old "beaver" facing NNE. Placed a squared cedar post adjacent. Distances are to meas. notch. Bearings are magnetic.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 12/29/98

For the Michigan Department of Natural Resources - Forest Management Division