

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>34W</u>	<u>F5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____



4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 04 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (F5) Quarter corner common to 9-16. Established in 1852 by Zelotes B. Searles: "40.125 Set quarter Sec. post. Spruce 8 S85W 5, Spruce 8 N32E 12." Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

(F5) Re-monumented the corner at the point remains of an old wood post and the probable remains of the 2 spruce bearing trees. The post point was found, rotted off at the water table, at record bearing and distance from both a rotting spruce stump, 20" in dia. with remains of a blaze and axe marks visible, N32E 8.3', and the root remains of a long-ago rotted spruce, S85W 3.3'. The distance west to a re-monumented corner is 39.523 ch. which is at odds with the record, but the measured distance 121.0421 ch. east checks well with the original 120.925 chains. A reestablished corner is 40.164 ch. east. At the position of the post-point, I placed a 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner was placed and witnessed by D.Lampela and B.Wheel@r, Baraga District Office. Corner is in a large alder swamp.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

(F5) Set 1" pipe with 4" MDNR cap.
 Blazed and scribed the following:
 6" 8. Spruce N39W 20.0' "1/4S NBT"
 12" Cedar S33W 18.45' do
 10" Cedar S12E 22.6' do
 12" Cedar S60E 38.8' do
 Placed a cedar post adjacent. Bearings are magnetic. Distances are to meas. notch.



Signed by Stephan J. Szyszkoski Date 12/29/98
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division