

50.

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>34W</u>	<u>ES</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>21</u> T <u>46N</u> R <u>34W</u>	<u>2</u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

2 Aug 04 1998  
ES Aug 25 1998

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5					●								
6	18	17	16	15	14	13							
7							●						
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(ES) Corner common to Sections 8-9-16-17. Established in 1852 by Zelotes B. Searles: "80.00 Set post Cor. of Secs. B, 9, 16, 17. Tan 4 S41 1/2W 89, do 4 N21E 19." August 1954 record by B.G. Buell for Northern Paper Mills at Med Lake Timber and Land Co. state: "1930. M. Cole and R. Sillers found orig. post. No evidence of B.T.s. Set post. 1954 Peryan and Wickman found Cole's post. No trace of BTs or original post. Set pipe at post. Description of corner monument: Pipe and brass cap. Witnesses: Bog, no trees big enough". Found no subsequent record.


(2-Sec. 21) East 1/16 corner between Sections 16-21. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(ES) Recovered the 1954 monument as described, a 1" ID iron pipe capped with a 2" brass tablet stamped "NORTHERN PAPER MILLS", marked with the incorrect section numbers 8-9-17-18, in good condition. Also found the remains of a post point adjacent and an old squared post 1 ft. easterly. Found no trace of the original BTs. The post point may possibly be the "orig. post" referred to in the 1954 record. I accept the monument as the best available evidence of the position of the original corner. Left the monument in place and marked new bearing trees as described below. Corner recovered and re-witnessed by B. Wheeler and D. Lampela, Baraga District Office. Two of the NBTs marked had metal location posters attached to them: 3" B. Spruce with a newer poster, 2" Tan. SW with an old one. (2-Sec. 21) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a line of mean true bearing between Quarter corner 1318.10' West and Section corner 1318.10' East. At the position for the corner I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D. Lampela and B. Wheeler, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(ES) Found 1" pipe with 2" MPH cap.	(2) Set 1" pipe with 4" MDNR cap.
Blazed and scribed the following:	Blazed and scribed the following:
3" B. Spruce N83E 21.9' "S9 NBT"	24" W. Pine N89W 23.5' "1/16S BT"
2" Tan. S57E 36.8' "S16 NBT"	10" Cedar N30E 9.2' do
2" Tan S38N 36.5' "S17 NBT"	10" Cedar S66E 28.8' do
2" B. Spruce N65W 3.15' "S8 NBT"	10" Cedar S29W 65.8' do
Squared and scribed B. Spruce post adjacent. Bearings are magnetic. Distances are to meas. notch.	Placed a squared cedar post adjacent. Distances are to meas. notch. Bearings are magnetic.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 12/29/98

For the Michigan Department of Natural Resources - Forest Management Division