

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron _____	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 46N R 34N	G3
	T 46N R 34W	F6
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

F6 Aug 26 1998

G3 Aug 25 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3						●						
4	7	8	9	10	11	12						
5												
6	10	17	●	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(G3) Corner common to Sections 3-4-9-10. Established in 1852 by Zelotes B. Searles: "S6°N Corrected...78.70 Set post Cor. Secs. 3,4,9,10. Spruce 3 S44E 25, Cedar 8 N50W 17". Aug. 24, 1954 record by B.G. Buell for Northern Paper Mills at Ned Lake Land and Timber Co. state: "1930 Jacobson and R.Sillers found Ced. 8 N50W 17 I.M. plain. Aug. 1954 S. Wickman and J.Peryan found post. No evidence of original 8.T. set pipe at post. Description of corner monument: Iron pipe and Brass cap. Witnesses: Ced. 8 N35E 30 lks., Ced. 8 S54W 25 lks." Found no subsequent record.

(F6) Center of Section 16. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G3) Recovered the 1954 monument, as described, a 1" ID iron pipe capped with a 2" dia. brass tablet stamped "NORTHERN PAPER MILLS", in good condition, and at record bearing and distance from the remaining 1954 witness Cedar NE. The Cedar SW appears to have fallen over. Found an old squared post adjacent to the monument. The original 8T's were not recovered. Although not it is not stated so in the 1954 record, I assume that the monument was placed at the position recovered in 1930. Distances West and South to probable original corners are 79.998 ch. (80.07R) and 40.169 ch. (40R) respectively. I accept the monument as a careful and faithful perpetuation of the position of the original corner. Left the monument in place and marked 3 new accessories as described below. Corner recovered and witnessed by D.Lampela and B.Wheeler, Baraga District Office.

(F6) Found no evidence of prior monumentation at the corner position. Established the corner at the intersection of straight lines connecting opposite quarter corners. At the position for the corner, I placed a 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G3) Found 1" iron pipe with MPH cap.

Blazed and scribed the following:

7" Cedar S47E 22.9' S10 NBT

8" Cedar S40W 18.8' S9 NBT

11" Cedar N47W 24.3' S4 NBT

The 1954 witness:

9" Cedar N39E 19.8' fd. scribed "S3 BT"

Bearings are magnetic. Distances to meas. notch.

(F6) Set 1" pipe with 4" MDNR cap.

Blazed and scribed the following:

4" 8. Spruce N35W 15.8'

5" 8. Spruce S48E 33.3'

5" 8. Spruce S21E 16.6'

5" 8. Spruce S48W 30.85'

Placed a squared cedar post adjacent.

Bearings are magnetic. Distances are to meas. notch.



Signed by

Stephan J. Szyszkoski

Surveyor's Michigan License No.

33986

Date

12/29/98

For the Michigan Department of Natural Resources - Forest Management Division