

54.

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 46N R 34W	F3
	T 46N R 34W	F4
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Aug 10 1998

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5											
3						●							
4	7	8				●	10	11	12				
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(F3) Quarter corner common to Sections 4-9. Established in 1852 by Zelotes B. Searles: "S89 deg. 41'N Corrected... 40.03 1/2 Set post quarter Sec. Tam 4 S40W 13, Cedar 4 N27E 5". Found no subsequent record.

(F4) Center of Section 9. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F3) Original post and accessories were not recovered. Found no evidence of prior monumentation at the corner position. Found no acceptable evidence of the position of the original corner on the ground. Found several blazed cedars in the area, including one with a Northern Paper Mills tag marked "about 1/4" which seems to mark an approximate corner. Reestablished the corner midway and on a line of mean true bearing between monumented corners 39.989 ch. East and West, being proportionate to the original record. I observed the true bearing of this line as S89 deg. 37'54"W. At the position for the corner I placed a 1" ID x 60" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by B.Wheeler and D.Lampela, Baraga District Office.

(F4) Found no evidence of prior monumentation at the corner position. Established the corner at the intersection of straight lines connecting opposite quarter corners. At the position for the corner I placed a 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F3) Set 1" pipe with 4" MDNR cap.

Blazed and scribed the following:

12" Cedar N85E 15.2' "1/4S NBT"

8" Cedar N64W 36.5' "1/4S NBT"

8" Cedar (leaning) N39E 50.6' do

7" Bl. Ash S45W 22.5' "1/4S NBT"

Placed a squared cedar post adjacent.

Distances are to meas. notch. Bearings are magnetic.

(F4) Set 1" pipe with 4" MDNR cap.

Blazed and scribed the following:

6" B. Spruce N24E 29.7' "C1/4S BT"

8" B. Spruce S71E 24.0' do


8" B. Spruce S38W 19.1' do

6" B. Spruce N57W 16.2' do

Placed a squared B. Spruce post

adjacent. Bearings are magnetic.

Distances are to meas. notch.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 12/29/98

For the Michigan Department of Natural Resources - Forest Management Division