

SURVEY & REMONUMENTATION

FORM NO. 985-A



Stock No. 26273

MAR 19 1997

COMMISSION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>34W</u>	<u>D-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

96 DEC 23 AM 9:03
L.C. Records L. 7, P. 45
Gilbert J. Pisoni
REGISTERED DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter corner between Sections 20 & 29, T46N R34W

I, Gary L. Pisoni, in a field survey on October 22, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Z.B. Searls, U.S. Deputy Surveyor on July 9, 1852.
Original corner: Wood Post
Original bearing trees:

White Pine	30"	S 25° E	Unknown
White Pine	28"	N 75° W	10 Links (6.60 feet)

On June 14, 1978, Robert E. Schmeling, R.L.S. set a 1" dia. By 4 feet long galvanized iron pipe with a brass cap from evidence of original bearing trees as described above.
Recorded in Land Corner Certificate L. 1, Page 550 on August 10, 1978.

1978 bearing trees:

White Pine	8"	N 42° E	33.3 feet
White Spruce	12"	S 22° E	38.6 feet
White Spruce	7"	S 67° W	52.0 feet
White Spruce	10"	N 28° W	11.5 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found the monument and bearing trees as described above.

White Pine	12"	N 46° E	33.32 feet
White Spruce	14"	S 20° E	38.38 feet
White Spruce	9"	S 70° W	51.49 feet
Wood Post	6" x 6"	S 70° W	1.10 feet


Corner Record Research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the above described brass cap monument, I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

White Spruce	10"	N 32° W	24.32 feet
Steel Sign Post	6'	N 10° W	0.90 feet

PEER GROUP APPROVED
Gary L. Pisoni 12-11-96
COUNTY REPRESENTATIVE



#96-23
Signed by Gary L. Pisoni Date 12-10-96
Surveyor's Michigan License No. 27457

L. 7 P. 45