

**SURVEY & REMONUMENTATION**

FORM NO. 985-A



MAR 19 1997

Stock No. 26273

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

96 DEC 23 AM 9:03

*L.C. Records L.7, P.47*

*Gary L. Pisoni*  
REGISTERED LAND SURVEYOR

Register of Deeds Stamp & File Number

or corners in

Iron

(County)

Located In:

Corner Code #

1. Public Land Survey

T 46N R 34W

F-13

T 45N R 34W

F-1

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Quarter corner S.33, T46N R34W  
S. 4, T45N R34W

Gary L. Pisoni, in a field survey on October 19, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

6. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor on September 18, 1846.

Original corner: Fir Post

Original bearing trees:

Elm	14"	N 76° E	46 Links (30.36 feet)
Elm	10"	N 15° W	5 Links ( 3.30 feet)

7. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 1" dia. iron pipe with a 4" aluminum Department of Natural Resources cap and 3" x 3" x 5 foot long wood post at corner position set by R.L.S. #19006 stamped to read T45-46N, R34W, 1/4, 33, 4, RLS 19006, no recorded land corner certificate found in Register of Deeds office in Iron County.

Bearing trees:

Sugar Maple	13"	N 23° E	38.11 feet
Sugar Maple	15"	N 83° W	29.24 feet

Corner Record Research on file with County Representative.

PEER GROUP APPROVED


*Iron Gary L. Pisoni 12-11-96*

COUNTY REPRESENTATIVE

8. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the above described aluminum monument, I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Sugar Maple	9"	S 85° E	49.13 feet
Sugar Maple	7"	S 17° E	43.67 feet
Steel Sign Post	6'	N 32° E	1.10 feet



96-25

Signed by *Gary L. Pisoni*

Date 12-10-96

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975

REVISED JAN., 1983

REVISED OCT., 1995

*L.7 P.47*