

SURVEY & REMONUMENTATION

FORM NO. 985-A



Stock No. 26273

MAR 19 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron
(County)

Located In:

Corner Code #

1. Public Land Survey

T 46N R 34W H-13
T 45N R 34W H-1

2. Property Controlling in Section

S ___ T ___ R ___
S ___ T ___ R ___

3. Miscellaneous Property in Sec.

S ___ T ___ R ___
S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner between S.34, T46N R34W
S.3, T45N R34W

I, Gary L. Pisoni, in a field survey on October 19, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor on September 18, 1846.
Original corner: Sugar Post
Original bearing trees:
Sugar Maple 12" N 05° E 18 Links (11.88 feet)
White Pine 30" N 55° W 29 Links (19.14 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 2" x 2" x 4 foot wood stake marking corner position. Found a white pine bearing tree stump at correct bearing and distance from wood stake. G.L.O. distance check good East and West from wood stake to other G.L.O. corners.

Corner Record Research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, I set a 3/4" outside diameter by 3 feet long aluminum rod monument with a 3" cast aluminum cap, stamped to read: Iron County Remonumentation, T46N, R34W, 1/4, S-34, S-3, T45N, 1996, RLS-27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Red Maple	11"	N 68° E	4.80 feet
Sugar Maple	9"	S 27° E	45.68 feet
Sugar Maple	13"	S 26° W	34.96 feet
Black Cherry	12"	N 71° W	17.89 feet
Steel Sign Post	6'	N 20° E	1.00 feet

IRON COUNTY MICHIGAN
RECEIVED FOR RECORD

96 DEC 23 AM 9:02
L.C. Records L. 7, P. 44
Gary L. Pisoni
REGISTERED LAND SURVEYOR

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

PEER GROUP APPROVED
Gary L. Pisoni 12-11-96
COUNTY REPRESENTATIVE



#96-22
Signed by Gary L. Pisoni
Surveyor's Michigan License No. 27457

Date 12-10-96

L.7 P.44