

SURVEY & REMONUMENTATION

FORM NO. 985-A



MAR 19 1997

Stock No. 26273

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron
(County)

Located In:

Corner Code #

1. Public Land Survey

~~T46N R34W~~ K-1

T 45N R 34W K-1

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

IRON COUNTY MICHIGAN RECEIVED FOR RECORD

96 DEC 23 AM 9:04

L.C. Regoula L. 7, P. 49

Gilbert J. Pisoni
REGISTERED LAND SURVEYOR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Section Corner 35 & 36, T46N R34W
2 & 1, T45N R34W

I, Gary L. Pisoni, in a field survey on October 19, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor on September 18, 1846.

Original corner: Tamarack Post

Original bearing trees:

Tamarack	7"	N 27° E	20 Links (13.20 feet)
Tamarack	6"	N 49° W	74 Links (48.84 feet)

Original Subdivision established by Guy H. Carleton, U.S. Deputy Surveyor on July 12, 1851.

Original bearing trees:

Tamarack	6"	S 09° W	43 Links (28.38 feet)
Spruce	6"	S 72° 30' E	47 Links (31.02 feet)

In 1932, B.G. Buell found 4 bearing tree stumps and set wood post.

In 1953, Wickman found Buell's post and set a 1" dia. iron pipe with Northern Paper Mills brass cap

1953 bearing trees:

Tamarack	4"	N 19° E	51.5 Links (33.99 feet)
Tamarack	4"	S 38° W	18.3 Links (12.08 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found monument and bearing trees as described above.

Tamarack	6"	N 18° E	34.31 feet
Tamarack	7"	S 42° W	12.35 feet

Corner Record Research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing trees: (all measurements taken to a nail in side of tree)

Black Spruce	6"	S 26° E	7.18 feet
Black Spruce	7"	N 13° W	22.54 feet
Steel Sign Post	6'	South	0.60 feet

96-27

Signed by Gary L. Pisoni

Date 12-10-96

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS. JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995

L. 7 P. 49

PEER GROUP APPROVED

Iron Gary L. Pisoni 12-11-96

COUNTY REPRESENTATIVE

