

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Iron</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>34W</u>	<u>F10</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S <u>28</u> T <u>46N</u> R <u>34W</u>	<u>9</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File  
Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Jul 20 2005

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		●●		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(F10) Center of Section 28. Not established in the original survey. Found no subsequent record.  
 (9-Sec. 28) East 1/16 corner Section 28. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F10) Established the corner at the intersection of straight lines connecting opposite Quarter corners.  
 (9-Sec. 28) Established the corner midway and on a straight line between Center of Section 1316.98' West and Quarter corner 1316.98' East. The corner position falls about 15' West and 33' South of the NW corner of a clearcut.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F10) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 10" Sugar N40E 23.2'    mrkd "C1/4 BT" 5" Sugar S17E 2.2'        do 28" Hemlock S37W 20.4'    do 22" Sugar N76W 44.9'        do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.	(9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 7" Sugar N01W 11.2'    mrkd "1/16S BT" 5" Sugar N71E 18.2'        do 6" Sugar S21E 27.1'        do 5" Maple S87W 10.3'        do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
--	---



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 8/25/05