

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>34W</u>	<u>K5</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>13</u> T <u>46N</u> R <u>34W</u>	<u>11</u>
	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on Sept. 10, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5										●		
6	18	17	16	15	14	13				●		
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (K5) Corner common to Sections 11-12-13-14. 1852 - Established by Z.B.Searls, Deputy Surveyor. Set post. Spruce 4 N71E 41 links, Spruce 8 S68E 40 links. Found no subsequent record.

(11-Sec. 13) Southwest 1/16 corner, Section 13. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (K5) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner by double proportionate measurement to the original record between Section corner 10433.65' north (GLO = 158.40 chains), Section corner 5270.01' east (GLO = 80.19 chains), Section corner 5269.54' south (GLO = 80.00 chains), and Quarter corner 2629.05' west (GLO = 40.00 chains). From the position thus established, I found the unmaintained remains of an old fence post line running north, 28' east, and an iron pin, possibly some type of axle, N70E, 26' distant, it being 3' west of the fence post line, which I did not accept as evidence of the position of the original corner.

(11-Sec. 13) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (K5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. (11) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in: Set measuring nail with MDNR tag in:
 15" W.Pine N83E 95.7' mrkd "S12 NBT" 4" Tamarack N08E 18.7' mrkd "1/16S BT"
 5" Balsam S36E 46.2' "S13 NBT" 5" Spruce N70E 2.2' do
 5" Spruce S09E 64.4' "S13 NBT" 6" Spruce S69W 18.2' do
 5" Spruce S08W 66.1' "S14 NBT" 5" Spruce N54W 13.0' do
 Set sq'd cedar post adjacent. Brgs are magnetic. Set sq'd spruce post adjacent. Brgs are magnetic.
 Dist. are to nail with tag in the side of tree. Dist. are to nail with tag in the side of tree.

Signed by Stephan J. Szyszkoski



Surveyor's Michigan License No. 33986

Date 11/6/07