

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T46N R 34W</u>	<u>K6</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	<u>S 24 T46N R 34W</u>	<u>5</u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File
Number

4. Lot No. , Recorded Plat
 5. Private Claims

K6 Sep 10 2007
5 Jun 05 2007

I, Stephan J. Szyszkoski, in a field survey on , 20 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14	●	13	
7													
8		19		20		21		22		23		24	●
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (K6) Quarter corner common to Sections 13 and 14. 1852 - Established by Z.B.Searls, Deputy Surveyor, midway and on the Section line between Section corners 40.00 chains north and south. Set post. Fir 8 S10E 18 links, Fir 8 N71W 25 links. Found no subsequent record.

(5-Sec. 24) North 1/16 corner, Section 24. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (K6) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner by single proportionate measurement to the original record, midway and on the Section line between Section corners 2634.77' north and south.

(5-Sec. 24) Established the corner midway and on a straight line between Quarter corner 1320.45' north and Center of Section 24 1320.45' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (K6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set a measuring nail with MDNR tag in:
 7" Spruce N45W 14.8' mrkd "1/4S NBT"
 4" Tamarack N16E 2.2' do
 5" Spruce S79E 12.1' do
 5" Balsam S44E 13.6' do
 Set sq'd spruce post adjacent. Brgs. are magnetic. Distances are to nail with tag in the side of tree.
 (5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in:
 10" Tamarack S30E 18.1' mrkd "1/16S BT"
 10" Spruce S09W 39.4' do
 11" Cherry S52W 10.1' do
 10" Cherry N20W 29.1' do
 Set sq'd cedar post adjacent. Brgs. are magnetic. Dist. are to nail with tag in the side of tree.



Signed by Stephan J. Szyszkoski

Date 11/6/07

Surveyor's Michigan License No. 33986