

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T46N R 34W	K9	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims			

Register of Deeds Stamp & File Number

I, Stephan J. Szyszkoski, in a field survey on Sept. 12, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (K9) Corner common to Sections 23-24-25-26. 1852 - Established by Z.B.Searls, Deputy Surveyor. Set post. Spruce 12 S36E 16 links, Fir 12 N15W 23 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (K9) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner by double proportionate measurement to the original record between Quarter corner 2640.78' north (GLO = 40.19 chains), Section corner 5271.09' east (GLO = 80.20 chains), Section corner 10562.26' south (GLO = 160.75 chains), and Quarter corner 2641.11' west (GLO = 40.18 chains).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (K9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in:
 6" Balsam N28E 12.8' mrkd "S24 NBT"
 11" Spruce S63E 32.1' "S25 NBT"
 12" Spruce S15W 29.2' "S26 NBT"
 8" Balsam N49W 20.2' "S23 NBT"
 Set sq'd spruce post adjacent. Bearings are magnetic.
 Distances are to nail with tag in the side of tree.



Signed by Stephan J. Szyszkoski Date 11/6/07

Surveyor's Michigan License No. 33986