

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

|  |             |               |  |
|--|-------------|---------------|--|
| <u>Iron</u><br><small>(County)</small> | Located In: | Corner Code # |  |
| 1. Public Land Survey                  | T46N R 34W  | L7            |  |
|  | T46N R 34W  | M4            |  |
|  | T R         |               |  |
|  | S T R       |               |  |
| 2. Property Controlling in Section     | S T R       |               |  |
|  | S T R       |               |  |
| 3. Miscellaneous Property in Sec.      | S T R       |               |  |
|  | S T R       |               |  |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims

M4 Jun 05 2007  
 L7 May 31 2007

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(L7) Quarter corner common to Sections 13 and 24. 1852 - Established by Z.B.Searls, Deputy Surveyor, midway and on the section line between Section corners 40.00 chains east and west. Set post. Spruce 12 West 8.49, no other tree near. Found no subsequent record.

(M4) Quarter corner common to Section 12 T46N-R34W and Section 7 T46N-R33W. 1846 - Established by Austin Burt, Deputy Surveyor, midway and on the Range line between Section corners 40.00 chains north and south. Set Sugar post. Fir 11 S10E 12 links, Fir 11 N27W 28 links. Found no subsequent record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(L7) The original post and accessory were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner midway and on the section line between Section corners 2639.51' east and west. The corner falls in an alder swamp and there are no trees suitable for use as accessories.

(M4) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner by single proportionate measurement to the original record, midway and on the Range line between Section corners 2638.84' north and south.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

|  |   |
|--|---|
| (L7) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. The corner falls in an alder swamp and there are no trees suitable for use as accessories. Set sq'd spruce post 1' north of the corner. Set sq'd Cedar post 1' south of the corner. | (M4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set a measuring nail with MDNR tag in:<br>4" Spruce S26E 50.2' mrkd "1/4S NBT"<br>12" Spruce N45E 44.7' do<br>9" Spruce N11W 39.7' do<br>8" Spruce S21W 56.1' do<br>Set sq'd spruce post adjacent. Brgs. are magnetic. Distances are to nail with tag in the side of tree. |
|--|---|

|    |   |    |   |    |   |    |   |    |   |    |   |    |   |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1  | A | B  | C | D  | E | F  | G | H  | I | J  | K | L  | M |
| 2  |   | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 4  |   | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 | ● |
| 5  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 6  |   | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |   |    |   |    |   |    |   |    |   |    |   | ●  |   |
| 8  |   | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 |   | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 |   | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |   |    |   |    |   |    |   |    |   |    |   |    |   |



Signed by Stephan J. Szyszkoski Date 11/6/07

Surveyor's Michigan License No. 33986