

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T46N R 34W</u>	<u>M6</u>
	<u>T46N R 34W</u>	<u>M8</u>
	T ___ R ___	_____
	S ___ T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims

M8 May 31 2007  
 M6 May 30 2007

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(M6) Quarter corner common to Section 13 T46N-R34W and Section 18 T46N-R33W. 1846 - Established by Austin Burt, Deputy Surveyor, midway and on line between Section corners 40.00 chains north and south. Set spruce post. Spruce 14 S68E 23 links, Y.Birch 16 N27W 21 links. Found no subsequent record.

(M8) Quarter corner common to Section 24 T46N-R34W and Section 19 T46N-R33W. 1846 - Established by Austin Burt, Deputy Surveyor, midway and on the Range line between Section corners 40.00 chains north and south. Set Sugar post. Maple 10 S25W 10 links, Y.Birch 18 S87E 24 links. Found no subsequent record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(M6) The original post and accessories were not recovered. Found a 1"ID iron pipe, bent but with lower portion undisturbed and plumb, at substantial record bearing and distance from Township corner 13103.18' north and Quarter corner 2648.20' south. The found pipe is 0.50' east of a line between these two corners. Accepted same as the best available evidence of the position of the original corner.

(M8) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner midway and on the Range line between monumented Section corners 2640.47' north and south.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(M6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap made firm in a mound of rock. Set a measuring nail with MDNR tag in:  
 14" W.Spruce N47E 40.6' mrkd "1/4S NBT"  
 5" B.Spruce S85E 46.2' do  
 8" W.Spruce S45E 48.7' do  
 11" Maple S06W 34.7' do  
 Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag in the side of the tree.

(M8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set a measuring nail with MDNR tag in:  
 8" Sugar N71E 28.3' mrkd "1/4S NBT"  
 6" Sugar S49E 27.6' do  
 8" Sugar S54W 10.2' do  
 7" Sugar N53W 4.1' do  
 Set sq'd Sugar post adjacent. Brgs are magnetic. Dist. are to nail with tag in the side of tree.



Signed by Stephan J. Szyszkoski

Date 11/6/07

Surveyor's Michigan License No. 33986