

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Iron	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 19 T 46N R 34W	4
	S 19 T 46N R 34W	8
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Jul 21 2005

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- (4-Sec. 19) Northwest 1/16 corner, Section 19. Not established in the original survey. Found no subsequent record.
- (8-Sec. 19) West 1/16 corner, Sec. 19. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (4-Sec. 19) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. From the position thus established, I found a 1/2" dia. rebar projecting 2.5', S67E 16.3' distant, which I did not accept for the corner.
- (8-Sec. 19) Established the corner at 20.00 chains, proportionate to the dimensions derived from the original GLO plat, west of the Center of Section 19, and on a straight line between the Center of Section and the West 1/4 corner of Section 19, the position being 1323.66' West of the Center (20.00 ch. R) and 1239.28' East of the West 1/4 corner (18.725 ch. R). From the position thus established, I found a 1/2" rebar projecting 2.5', N86E 40.5' distant, which I did not accept for the corner. It appears the rebar was placed by someone who intended to mark the midpoint between the Center of the Section and the West 1/4 corner, that method being improper for this particular corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |  |  |
|--|--|
| (4) Set 1"IDx32" I.pipe with 4" alum.<br>MDNR cap. Set measuring nails in:           | (8) Set 1"IDx32" I.pipe with 4" alum.<br>MDNR cap. Set measuring nails in:           |
| 7" Sugar N83E 15.5' mrkd "1/16S BT"  | 4" Sugar N43E 12.0' mrkd "1/16S BT"  |
| 17" Cedar S50E 40.5' do  | 5" Sugar S15E 14.2' do   |
| 6" Sugar S08W 21.7' do   | 7" Sugar S78W 18.6' do   |
| 6" Sugar S66W 19.2' do   | 6" dbl Sugar N49W 21.2' do   |
| Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. | Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. |



Signed by *Stephan J. Szyszkoski* Date 8/25/05  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities