

MAY 28 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

COUNTY MICHIGAN

96 DEC 10 PM 3: 32

L. J. P. II
Richard L. Leemon
REGISTERED LAND SURVEYOR

FOR CORNERS OF --	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>46N</u> N. S., R. <u>37W</u> E. W.	G1
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on August 15, 1996, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Section corner common to sec's. 3 & 4 of T46N R37W and sec's. 33 & 34 of T47N R37W

- 1847 survey by Wm. A. & Austin Burt Set Sugar Post, (1) Sugar 24 N58E 34 links, (2) Sugar 9 N5W 24 links
- 1851 survey by Elias C. Martin Fd. Post (3) Sugar 14 S49W 33 links, (4) Sugar 16 S20E 33 links
- 1972 survey by Donald D. Lappala #12585 Set 2.5"x60" I.P. w/brass cap from wit's. 1 through 4, (5) Elm 11 N08E 11.9 ft., (6) S.Maple 7 East 6.9 ft., (7) Elm 8 S65W 13.5 ft.
- 1988 recovery by Gerald Koski U.S.F.S. Fd. 2.5"x60" I.P., (8) S.Maple 6 S42E 20.03 ft., (9) S.Maple 6 S45W 23.35 ft.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I found the 2.5"x60" Iron Pipe filled with concrete w/brass cap by Lappala in good condition. Witnesses 1 through 4 are gone. Witness 5 through 9 are stumps. A corner certificate was filed in the Iron County Court House by Lappala. This monument is accepted as a careful and faithful perpetuation of the position of the original corner.

County Research and Field Search information is on file with the County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Section corner common to sec's. 3 & 4 of T46N R37W and sec's. 33 & 34 of T47N R37W
Monu. The 2.5"x60" Iron Pipe filled with concrete w/brass cap was left in place.

- Witnesses:
- 60d spike in the east side of a S.Maple 9 N34W 30.42 ft.
 - 60d spike in the east side of a S.Maple 11 N01W 31.05 ft.
 - 60d spike in the south side of a S.Maple 10 N71E 29.06 ft.
 - 60d spike in the north side of a S.Maple 12 S71W 62.15 ft.
 - N1/4 3 S89-58-12E 2648.73 ft.
 - W1/4 3 S00-26-20'E 2623.00 ft.

SIGNED BY *Patrick R. Leemon* DATE August 15, 1996

SURVEYOR'S MICHIGAN REGISTRATION NO. 31595

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. L. J. P. II