

# LAND CORNER RECORDATION CERTIFICATE

MAY 28 1997

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

COMMISSION

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 46N N. S., R. 37W E. W.	G2
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD  
86 DEC 10 PM 3:33  
*L.C. Reynolds L.P. 16*  
*Edwin Stobie*  
REGISTER OF DEEDS  
REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on August 15, 1996, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

**1/4 Corner common to sections 3 & 4 of T46N R37W**

1851 survey by Elias C. Martin Set Sugar Post, (1) Y. Birch 12 N52W 50 links, (2) Y. Birch 12 S75E 32 links  
1972 survey by Donald D. Lappala #12585 Set 2.5"x60" I.P. w/brass cap from wit's. 1 and 2, (3) S. Maple 9 N28W 21.6 ft., (4) S. Maple 5 N10E 7.4 ft., (5) S. Maple 4 S39E 11.0 ft.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I found the 2.5"x60" Iron Pipe filled with concrete w/brass cap by Lappala in good condition. Witnesses 1 and 2 are gone. Witness 5 is a stump. Witnesses 3 and 4 are in good condition. Lappala filed a corner certificate in the Iron County Court House. This monument is accepted as a careful and faithful perpetuation of the position of the original corner.

County Research and Field Search information is on file with the County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**1/4 Corner common to sections 3 & 4 of T46N R37W**

Monu. The 2.5"x60" Iron Pipe filled with concrete w/brass cap was left in place.  
Witnesses:  
R. Maple 15 S88E 25.45 ft.  
R. Maple 9 N53E 19.41 ft.  
60d spike in the south side of a S. Maple 5 N15E 7.55 ft.  
60d spike in the west side of a S. Maple 10 N25W 21.80 ft.  
Wood Post 4x4 N75W 2.86 ft.  
NW 3 N00-26-20W 2623.00 ft.  
SW 3 S00-56-56E 2627.56 ft.


SIGNED BY *Patrick R. Leemon* DATE August 15, 1996

SURVEYOR'S MICHIGAN REGISTRATION NO. 31595

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



*L. P. 16*

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_