

**LAND CORNER RECORDATION CERTIFICATE**

MAY 28 1997

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

**COMMISSION**

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>46N</u> N. S., R. <u>37W</u> E. W.	<u>I-1</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

96 DEC 10 PM 3:33

*L. H. P. 13*  
*Patrick R. Leemon*  
REGISTER OF DEEDS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on August 15, 1996, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

**Section Corner common to sec's 2 & 3 of T46N R37W and sec's. 34 & 35 of T47N R37W**

1847 survey by Wm. A. & Austin Burt Set Cedar Post, (1) Sugar 14 N35E 39 links, (2) Sugar 12 N50W 43 links  
1851 survey by Elias C. Martin Fd. Post (3) Hemlock 24 S31W 25 links, (4) Hemlock 18 S78E 31 links  
1936 search by Carl Weinert C.C.C. Fd. a cedar post

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I searched for but could not find evidence of the Burt corner. I did not find the cedar post called for by Carl Weinert. I recovered this corner by single proportional measurement between the NW 3 and the NE 2. The GLO feature calls support this location. This monument is intended to be a careful and faithful re-establishment of the original corner.

County Research and Field Search information is on file with the County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**Section Corner common to sec's 2 & 3 of T46N R37W and sec's. 34 & 35 of T47N R37W**  
Monu. Set a 2"x30" flared base aluminum pipe with aluminum cap and magnet.

Witnesses:  
S.Maple 3 N25W 9.75 ft.  
R.Maple 8 N45E 16.14 ft.  
R.Maple 9 S40E 13.59 ft.  
S.Maple 3 N75W 6.49 ft.  
NW 3 N89-58-12W 5297.46 ft.  
NE 2 S89-58-12E 5297.46 ft.  
E1/4 3 S 0-52-26E 2666.66 ft.

SIGNED BY Patrick R. Leemon DATE August 15, 1996

SURVEYOR'S MICHIGAN REGISTRATION NO. 31595

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



*L. H. P. 13*

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_