

**MAY 28 1997 LAND CORNER RECORDATION CERTIFICATE**

**COMMISSION FILING REQUIREMENT OF ACT 74, MICH. P.A.1970**

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 46N N. S., R37W E. W.	1-2
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S., R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

IRON COUNTY MICHIGAN  
 RECEIVED FOR RECORD  
 96 DEC 10 PM 3:33  
*RC Leemon d/P.17*  
*Patrick R. Leemon*  
 REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on August 15, 1996, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**1/4 Corner common to section 2 and 3 of T46N R37W**  
 1851 survey by Elias C. Martin Set Sugar Post, (1) Y. Birch 20 S30W 12 links, (2) Hemlock 30 N72E 42 links

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

I searched for but could not find evidence of the Martin corner. The area has been disturbed by logging and mineral exploration. The GLO call to a hill 1.4 chains north of the corner fits within 20 feet. There was also a significant depression that matches the bearing and distance to witness 2. I was not able to confirm that it was indeed a hemlock. I therefore recovered this corner by single proportionate measurement between the NE 3 and the SE 3. This monument is intended to be a careful and faithful re-establishment of the position of the original corner. County Research and Field Search information is on file with the County Representative.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**1/4 Corner common to section 2 and 3 of T46N R37W**  
 Monu. Set 2"x30" flared base aluminum pipe with aluminum cap and magnet.  
 Witnesses:  
 R. Maple 4 N85W 7.98 ft.  
 R. Maple 5 N57W 8.95 ft.  
 R. Maple 4 N15E 7.89 ft.  
 R. Maple 12 S65E 26.23 ft.  
 SE 3 S 0-52-26E 2640.25 ft.  
 NE 3 N 0-52-26W 2666.66 ft.

SIGNED BY *Patrick R. Leemon* DATE August 15, 1996


SURVEYOR'S MICHIGAN REGISTRATION NO. 31595

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

*L.7 P.17*



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_