

SURVEY &
REMONUMENTATION

MAY 28 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>46N</u> N. S., R. <u>37W</u> E. W.	<u>1-3</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD
96 DEC 10 PM 3:34
L.C. Leemon
Patrick R. Leemon
REGISTER OF DEEDS
REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on August 15, 1996, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Section Corner common to section 2, 3, 10 and 11 of T46N R37W

1851 survey by Elias C. Martin Set Sugar Post. (1) Spruce 14 S24W 44 links, (2) Y. Birch 14 N68E 55 links
1937 search by T.J. Hamalainen U.S.F.S. Fd. 1" iron post 36" above the surface and 20 links north of road.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I recovered the 3/4"x1" iron bar that Hamalainen found in 1937. I searched for evidence of the Martin survey, but found nothing. The GLO calls do not aid in the recovery. This position is only .51 ft. longer than record up to the township line. I accepted the iron bar as a careful and faithful perpetuation of the position of the original corner.

County Research and Field Search information is on file with the County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Section Corner common to section 2, 3, 10 and 11 of T46N R37W

Monu. Set 2"x30" flared base aluminum pipe w/aluminum cap and magnet.

Witnesses:

- 60d spike in the east side of a R. Maple 4 N50W 8.81ft.
- 60d spike in the north side of a R. Maple 6 N85E 18.63 ft.
- 60d spike in the west side of a Aspen 12 S29E 12.85 ft.
- 60d spike in the east side of a Aspen S20W 9.77 ft.
- E1/4 3 N 0-52-26 W 2640.25 ft. ^{12"}
- S1/4 3 N89-21-52W 2657.57 ft.

SIGNED BY Patrick R. Leemon DATE August 15, 1996

SURVEYOR'S MICHIGAN REGISTRATION NO. 31595

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____
MICHIGAN REGISTERED LAND SURVEYOR



L.7 P.20

SURVEYOR'S MICHIGAN REGISTRATION NO. _____