

SURVEY & REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

MAY 28 1997

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

COMMISSION

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>46N</u> N. S., R. <u>37W</u> E. W.	<u>J1</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

IRON COUNTY MICHIGAN
 RECEIVED FOR RECORD
 96 DEC 10 PM 3:33
L. G. P. 14
William J. Stibic
 REGISTER OF DEEDS
 REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on August 15, 1996, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

1/4 Corner common to section 2 of T46N R37W and section 35 of T47N R37W

1847 survey by Wm. A. & Austin Burt Set Sugar Post, (1) Hemlock 14 N72E 53 links, (2) Sugar 4 N31W 35 links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I searched for but could not find evidence of the Burt corner. I recovered this corner by single proportional measurement between the NW 3 and the NE 2. The GLO feature calls support this location. This monument is intended to be a careful and faithful re-establishment of the position of the original corner.

County Research and Field Search information is on file with the County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/4 Corner common to section 2 of T46N R37W and section 35 of T47N R37W

Monu. Set 2"x30" flared base aluminum pipe with aluminum cap and magnet.

Witnesses:

- S. Maple 7 N13W 10.49 ft.
- Y. Birch 7 N67E 12.43 ft.
- S. Maple 7 S29W 6.25 ft.
- Y. Birch 11 S68W 8.69 ft.
- NW 3 N89-58-12W 7946.19 ft.
- NE 2 S89-58-12E 2648.73 ft.

SIGNED BY *Patrick R. Leemon* DATE August 15, 1996


SURVEYOR'S MICHIGAN REGISTRATION NO. 31595

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

L. G. P. 14



SURVEYOR'S MICHIGAN REGISTRATION NO. _____