

SURVEY & REMONUMENTATION

JAN 12 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

IRON COUNTY MICHIGAN
RECEIVED FOR RECORD

95 APR 26 AM 11:10
L.6 L.C. RECORDS P. 389

Richard L. Drahn
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in <u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>37W</u>	<u>K-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
Section Corner 11, 12, 13 & 14; T.46N., R.37W.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Richard L. Drahn, in a field survey on June 14, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by E.C. Martin, U.S. Deputy Surveyor, on July 9, 1851. Original bearing trees:
Hemlock 12" S.66E. 21 links (13.86 feet)
Sugar Maple 18" N.70W. 23 links (15.18 feet)
Reference Land Corner Certificate by Donald D. Lappala, R.L.S. 12585, recorded in USFS Liber, Page J-21; on 2/27/75 of Iron Countie's records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Reconstruction of F.H. #16 required the removal and re-referencing of the section corner. After completion of the work, the corner was replaced as indicated below.

PEER GROUP APPROVED

Iron Hwy S. Room 3-1-95
COUNTY REPRESENTATIVE



Research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position in the blacktop of F.H. #16 I embedded a 3" brass cap stamped to read: T.46N., R.37W.; S-11, S-12, S-13, S-14; 1994; R.L.S. 21564 from which I established the following:

12"	Sugar Maple	N.82E.	52.51 feet
10"	Sugar Maple	N.84W.	44.00 feet
10"	Sugar Maple	N.58E.	66.75 feet

Brass capped Iron Pipe Reference Monument bears West 70.315 feet
Aluminum capped Aluminum Reference Monument bears East 70.315 feet
6' Steel Sign Post East 71.32 feet

Signed by Richard L. Drahn Date February 7, 1995

Surveyor's Michigan License No. 21564