

SURVEY & REMONUMENTATION

98318

APR 27 1995 REMONUMENTATION CORNER

COMMISSIONED CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ISABELLA
(County)

Located In:

Corner Code ##

- | | | | |
|------------------------------------|--------------------------|--|------------|
| 1. Public Land Survey | T <u>13N</u> R <u>4W</u> | | <u>C-5</u> |
| | T _____ R _____ | | _____ |
| | T _____ R _____ | | _____ |
| | T _____ R _____ | | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | | _____ |
| | S _____ T _____ R _____ | | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | | _____ |
| | S _____ T _____ R _____ | | _____ |

STATE OF MICHIGAN
COUNTY OF ISABELLA
RECEIVED FOR RECORD

MAR 23 11 PM '95

28
SHARON A. BROWN
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Wm. B. Ruddell, in a field survey on November, 1994 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|-----------------------|----------------------------------|
| 1838 - Post | 1980 - 1/2" Solid Rod |
| 1877 - Stake | 1984 - 1/2" Solid Rod |
| 1879 - Stake | 1991 - 1/2" Solid Rod |
| 1884 - Found corner | 1993 - 1/2" Solid Rod |
| 1972 - 1/2" Solid Rod | 1994 - Solid Rod in monument box |
| 1973 - 1/2" Solid Rod | |
| 1976 - 1/2" Solid Rod | |
| 1977 - 1/2" Solid Rod | |
| 1978 - 1/2" Solid Rod | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1994 - Augered down in monument box to depth of 3' ± - found no other evidence. Set standard monument.

And is accepted as a careful and faithful perpetuation of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1994 - Standard Monument, marked C-5, in existing monument box
 Witnesses: SE, 79.23', Nail & cap in Power Pole
 NNE, 76.45', Nail & cap in top of fence post
 SW, 55.9', Nail & cap in Power Pole
 SSE, 74.55', West corner of project marker

Signed by [Signature]
 Surveyor's Michigan License No. 14769

Date November 16, 1994

(51)