

**SURVEY &
REMONUMENTATION**

APR 29 1996

**REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

COMMISSION

For corners in

ISABELLA

(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>13N</u> R <u>5W</u> | <u>M-6</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

ST. CLAIR COUNTY OF MICHIGAN
RECEIVED
RECORD

MAR 14 3 49 PM '96

000:103 SHARON A. BROWN
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

WILLIAM B. RUDELL in a field survey on DECEMBER 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13	0					
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1837 - Hodgson
- 1877 - Found Old bearing trees - Set stake
- 1880 - Found Old bearing trees
- 1883 - Found old bearing trees - Set stake
- 1979 - Found 1" Pipe
- 1994 - Found 1" Pipe w/stone beside

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1994 - Found 1" Pipe verified location with LCRC 585
- Set Standard County remonumentation monument - marked A-6, M-6


ACCEPTED BY THE ISABELLA COUNTY
REMONUMENTATION PEER GROUP
ON 12/29/94
William B. Rudell
William B. Rudell, P.S.
County Representative

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set Standard County remonumentation monument - marked A-6, M-6
- Witnesses: Northeast, 76.55 feet, Nail & Cap in Fence Post- Northwest corner cattle loader
- East, 32.16 feet, Nail & Cap in Fence Post
- East, 54.95 feet, Nail & Cap in Power Pole
- Southeast, 172.35 feet, Nail & Cap in 18" Maple

Signed by *William B. Rudell*
Surveyor's Michigan License No. 14769



Date MARCH 5, 1996