

**SURVEY & REMONUMENTATION COMMISSION**  
**APR 29 1996**

**REMONUMENTATION CORNER  
 LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in Isabella Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey T 13N R 6W \_\_\_\_\_ G-3  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

STATE OF MICHIGAN  
 COUNTY OF ISABELLA  
 RECEIVED FOR RECORD  
 FEB 23 3 22 PM '96  
 000090  
 SHARON A. BROWN  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Gerald J. Gray, in a field survey on March 20, \_\_\_\_\_, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3							●						
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- Original G.L.O. Survey:  
 John Milroy D.S., set post corner to section 3,4,9, & 10, Nov. 17, 1837 - Dec. 4, 1837
- Joseph A. Graham Co. Surveyor, Found O.B.L. and stake, Feb. 8-11, 1882
- Joseph A. Graham found old corner stone "x" file under it, put there by Walmot McCabe, April 26 & 27
- L.C.R.C.  
 Thomas J. Mueller, 1/21/88  
 Found 5/8" bar in centerline of road north & south & ±5' north of centerline of road east & west
- Unrecorded Survey by Thomas J. Mueller, 1/20/88  
 Found 5/8" bar in centerline of road north & south & ±5' north of centerline of road east & west

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" bar in centerline of road north & south & 5'± feet north centerline of road east & west, Set standard Isabella County Monument in monument box

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Standard Isabella County Monument in Monument Box  
 124° AZ 57.90' Nail & cap in 4" cedar  
 39° AZ 95.02' Nail & cap in 16" catalpa  
 314° AZ 44.54' Nail & disk in telephone pole stub  
 265° AZ 207.50' Nail & cap in 10" white pine

ACCEPTED BY THE ISABELLA COUNTY  
 REMONUMENTATION PEER GROUP  
 ON Nov 8, 1994  
 William B. Ruddell, PS  
 County Representative

Signed by Gerald J. Gray Date 1-24-96  
 Surveyor's Michigan License No. 17741

