

SURVEY & REMONUMENTATION COMMISSION
APR 29 1996

**REMONUMENTATION CORNER
 AND CORNER RECORDATION CERTIFICATE**
 Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in Isabella Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey	T <u>13N</u> R <u>6W</u>	<u>K-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling S _____ T _____ R _____	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous S _____ T _____ R _____	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

STATE OF MICHIGAN
 COUNTY OF ISABELLA
 RECEIVED FOR RECORD
FEB 23 22 PM '96
000095
 SHARON A. BROWN
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Gerald J. Gray, in a field survey on March 20, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Original G.L.O. Survey:
John Milroy D.S., Nov. 17, 1837 - Dec. 4, 1837, set post for corner to section 1,2,11, & 12
- E. R. Coburn, Moore, Roberts, Chapman, 1887, set stone at section corner 8x8x12
- E. R. Coburn, Nov. 22, 1888, corner stone 8x8x12
- E. R. Coburn, 1901, Stone 10" for corner
- L.C.R.C.
John R. Radcliffe, Filing No. 270, 7/30/74
Gerald J. Gray, 3/91
- Survey of Record, Liber 004, Page 245, Jan S. Fokens, 11/18/86
- Unrecorded Survey by Gerald J. Gray, 4/15/91
- Unrecorded Survey by Gerald J. Gray, 6/6/91
- Unrecorded Survey by Gerald J. Gray, 8/17/93

- Found 1 1/2" pipe
- Found iron below pavement
- Found 1" pipe
- Found iron below pavement
- Found iron below pavement
- Found iron below pavement

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" iron below pavement, Set standard Isabella County Monument in monument box

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Standard Isabella County Monument in Monument Box
- 76° AZ 91.45' Spike in 10" Apple
 - 131° AZ 74.50' PK Nail in power pole
 - 226° AZ 52.50' PK Nail in telephone box post
 - 312° AZ 46.68' Spike in corner post

ACCEPTED BY THE ISABELLA COUNTY
 REMONUMENTATION PEER GROUP
 ON Nov 8 1998

 William B. Ruddell, FS
 County Representative

Signed by _____ Date 1-24-96

Surveyor's Michigan License No. 17741

