

SURVEY &
REMONUMENTATION

85256

MAR 16 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF ISABELLA
RECEIVED RECORD

Nov 30 11 32 AM '93

000015

Helene L. Blumrose
REGISTER OF DEEDS

For corners in
Isabella

(County)

Located In:

REMONUMENTATION
Corner Code #

	14N	3W	J-5
1. Public Land Survey	T	R	
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Norman C. Caldwell, in a field survey on July, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(J-5) 1/4 Cor., Sec. 11 & 14, T14N-R3W

Wood Post Placed by Joel Whight in 1832 Sub. of Twp: N30°E 9 L. (1.810M) 24" (61cm) Pine; S30°W 19 L. (3.822M) 12" (30.5cm) N. Maple.

L.C.R.C. by J. Jones, Recorded in Bk. 1 P. 414, Found 13mm Pipe: SE 13.259M Face C.P. Co. Gas Line Marker; SW 14.402M PK Nail in Service Pole; East 44.80M Prop. Cor. on Sec. Line.

L.C.R.C. by W. Ruddell, Recorded in Bk. 2 P. 823, Found 13mm Pipe: SW 14.402M PK in Service Pole; SE 13.259M Face Gas Line Marker; East 44.8M Prop. Marker.

Surveys by: Jones, L. 3, pg. 09, Mueller, L. 4, pg. 577, County Surveyor record in Book 3, pg. 116

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J-5) 1/4 Cor., Sec. 11 & 14, T14N-R3W

Found 20mm Iron Pipe per Bk. 1 P. 414 and Bk. 2 P. 823.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J-5) 1/4 Cor., Sec. 11 & 14, T14N-R3W

Found 20mm Iron Pipe per Bk.1 P. 414 and Bk. 2 P. 823, and is accepted as the best available evidence of the position of the original corner.
S50°E 13.266M Gas Line Marker (R)
S71°W 14.361M Power Service Pole (R)
S70°E 34.138M 20cm White Pine
S40°E 11.074M 20cm Scotch Pine



Signed by *Norman C. Caldwell*

Date 26 Nov 93

Surveyor's Michigan License No. 12018