

COMMISSION

85252

MAR 16 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF ISABELLA
RECEIVED RECORD

Nov 30 11 33 AM '93
000021

Nelda L. Helmre
REGISTER OF DEEDS

For corners in
Isabella

(County)

Located In:

REMONUMENTATION

Corner Code #

	14N	3W	M-6
1. Public Land Survey	T	R	
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman C. Caldwell, in a field survey on July, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(M-6) W 1/4 Cor., Sec. 13, T14N-R3W

Wood Post Placed by R. Clark in 1830 Survey of Twp. Bdry: S42°W 25L. (5.029M) 7" (18cm) Hemlock; N20°W 15L. (3.018M) 8" (20cm) Birch.

L.C.R.C. by J. Jones, Bk. 1 P. 414
Set 20mm Pipe Equidistant on line b/w M-5 & M-7:
NE 14.828M PK Nail in 10.4cm Maple; SW 25.055M PK Nail in 12.5cm White Birch.

Survey by Jones, L. 3, pg. 35

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M-6) W 1/4 Cor., Sec. 13, T14N-R3W

Found 46mm Iron Pipe in Mon. Box per Bk. 1 P. 414.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M-6) W 1/4 Cor., Sec. 13, T14N-R3W

Found 46mm Iron Pipe in Mon. Box per Bk. 1 P. 414, and is accepted as a careful and faithful reestablishment of the position of the original corner.

N50°E 14.828M 15cm Maple (R)
N70°W 24.343M 30.5cm Maple
S55°W 25.385M 25.5cm Tw. Maple
S70°E 18.080M 10.4cm White Pine
N75°E 12.888M 15cm Maple
North 21.458M 13mm Iron Rod



Signed by *Norman C. Caldwell*

Date 26 NOV 93

Surveyor's Michigan License No. 12018