

**SURVEY &
REMONUMENTATION**

APR 29 1996

**LAND CORNER RECORDATION CERTIFICATE COMMISSION
Filing Requirement of Act 74, Mich. P.A. 1970
Isabella County Remonumentation**

For Corners in
Isabella
(County)

Located In: Corner Code#:

- | | | |
|---------------------------------------|--------------------------------|-------------|
| 1. Public Land Survey | T. <u>15 N.</u> R. <u>3 W.</u> | <u>E-11</u> |
| | T. _____ R. _____ | _____ |
| | T. _____ R. _____ | _____ |
| 2. Public Controlling in Section | S. _____ T. _____ R. _____ | _____ |
| | S. _____ T. _____ R. _____ | _____ |
| 3. Miscellaneous Property in Section | S. _____ T. _____ R. _____ | _____ |
| | S. _____ T. _____ R. _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

STATE OF MICHIGAN
COUNTY OF ISABELLA
RECEIVED FOR _____ RD

Nov 30 3 34 PM '95
000067

SHARON A. BROWN
REGISTERED DEEDS

Register of Deeds Stamp & File Number


I, Jan S. Fokens, in a field survey on August, 1995, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													


NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Original G.L.O. Survey:
Township lines:
South Boundary June 1831 by Robert Clark
East Boundary Nov. 1831 by Harvey Parke
North Boundary May 1837 by John Hodgson
West Boundary April 1837 by John Hodgson
Subdivision & Re-survey 3rd quarter 1850 by Wm. A. Burt;
Page 70 original field notes
- Subsequent survey of record by County Surveyor N.R. Arnold;
Book 1 Dated 12/5/1871 (Section 28)
- L.C.R.C.
Liber 1, Page 146, A.V. Courtright 11/22/72
Liber 1, Page 255, D. Whittier 5/3/74
Liber 2, Page 616, P. Lapham 10/20/80
Liber 3, Page 838, Ruddell Engineering 12/23/86
Liber 3, Page 850, Ruddell Engineering 6/11/87
- Survey of Record
Liber 2, Page 105, Ruddell Engineering 7/14/75
- Unrecorded Surveys
Certified Survey by Land Surveying Consultants 11/1/94
Survey of Welneck Drain No. 650 by Land Surveying Consultants 1993



- Found 5/8" rod, 2" deep
- Found 3/4" rod
- Found iron bar
- Found rod
- Found 1/2" rod
- Found 5/8" rod
- Found 3/4" rod
- Found 1/2" re-rod



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

In a field survey on August 14, 1995, excavated and searched for the corner location:

- Found 3/4" dia. iron rod 24" long in top of 2"x2" wooden hub; top of hub 1.8' below surface of gravel road.
- Excavated 2.5' dia. hole to depth of 2.5'; found no further evidence of corner.

This corner established in Isabella County Remonumentation Program. See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set Standard Isabella County Monument in Monument Box.
- N.38°E., 77.00', Found spike in South side of utility pole E.11 to E.10 - 2648.85'
- N.42°W., 92.26', Nail and tag in NE. face of power pole E.11 to F.11 - 2649.29'
- S.56°W., 31.2', South end of 30" cmp
- S.40°E., 31.9', South end of 15" cmp

Signed by Jan S. Fokens
Surveyor's Michigan License No. 21567

Date Nov 17, 1995