

105350

SURVEY & REMONUMENTATION COMMISSION

APR 29 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Isabella County Remonumentation

COMMISSION

For Corners in Isabella

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 15 N. R. 3 W. G-10
2. Public Controlling in Section S. T. R.
3. Miscellaneous Property in Section S. T. R.
4. Lot No. Recorded Plat
5. Private Claims

STATE OF MICHIGAN COUNTY OF ISABELLA RECEIVED FOR RECORD

Nov 30 3 30 PM '95 000071

SHARON A. BROWN REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Jan S. Fokens, in a field survey on August, 1995, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

Table with 13 columns (A-M) and 13 rows (1-13) containing numbers 1-36 in a grid pattern.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. Original G.L.O. Survey: Township lines 2nd quarter by Robert Clark Subdivision & Re-survey 3rd quarter 1850 by Wm. A. Burt Page 56 & 58 original field notes
2. Subsequent survey of record by County Surveyor, N. R. Arnold, Book 1, 12/5/1871 (Sec. 28)
3. No L.C.R.C.
4. Survey of Record, Liber 1, Page 603, David B. Whittier 6/74
5. Unrecorded Survey Survey of Welneck Drain No. 650, Land Surveying Consultants Found iron Certified Survey by Land Surveying Consultants 11/1/94 Found 3/4" pipe

Vertical stamp: COUNTY OF ISABELLA COUNTY REGISTER OF DEEDS NOV 17 1995 WILLIAM E. FOKENS County Representative

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- In a field survey on August 14, 1995, excavated and searched for the corner location:
1. Found 3/4" pipe; 0.3' below gravel road.
2. Excavating 2.5' dia. hole to depth of 2'; found no further evidence of corner
This corner established in Isabella County Remonumentation Program. See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Standard Isabella County Monument in Monument Box. S.33°W., 64.48', LSC nail and tag in East face of 10" Red pine tree S.50°E., 43.90', LSC nail and tag in SW. face of 16" poplar tree S.78°E., 64.2', center 2" Red pine tree

G.10 to G.9 - 2639.53' G.10 to G.11 - 2640.51'

Circular seal: STATE OF MICHIGAN JAN S. FOKENS LAND SURVEYOR No. 21567

Recorded by [Signature] Surveyor's Michigan License No. 21567

Date Nov. 17, 1995