

SURVEY & REMONUMENTATION COMMISSION
APR 29 1995

REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in ISABELLA Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 16N R 5W E-13
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Section S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
 COUNTY OF ISABELLA
 RECEIVED FOR RECORD

DEC 11 10:38 AM '95
000036

SHARON A. BROWN
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, PAUL B. LAPHAM, in a field survey on OCTOBER, 19 95
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1837 HODGSON, G.L.O. 4-10-78 LAPHAM, (132)3-630-634
 FOUND CAPPED IRON
 WIT.-(6)N60°E 39.95' 6" MAPLE
 (7)S50°E 39.18' 6" MAPLE
 (8)S45°W 39.55' STEEL FENCE POST
 - 1850 BURT, G.L.O. RESURVEY SET POST
 WIT.-(1)HEMLOCK 8" N5°E 7 LKS.
 (2)HEMLOCK 8" N76°W 28 LKS.
 - 1899 DENSLOW, C.S.R. 3-131, C.S.R. 1-2
 BEECH STAKE 4x4 PERPETUATED BY W.H.T.
 ONE O.B.T. PRESERVED.
 WIT.-(3)PINE 18" S37°E 65
 (4)? 26" N41°W 40
 (5)BEECH STAKE EAST 50 & WEST 50
 - 9-20-78 LAPHAM, L.C.R.C. 494
 FOUND CAPPED IRON
 WIT.-(6, 7, & 8) ABOVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND 1"x16" PIPE AND PIECE OF IRON BESIDE IT. FOUND 6" MAPLE (NOW 10") N60°E 39.95'
 ALL OTHER WITNESSES GONE.

ACCEPTED BY THE ISABELLA COUNTY
 REMONUMENTATION PEEK GROUP
 ON 2/2/95
William B. Ruddell
 William B. Ruddell, PS
 County Representative

This Corner established in Isabella County Remonumentation Program.
 See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 E-13: 32 & 33 SECTION CORNER ON TOWNSHIP LINE.
 SET 1/2"x24" STANDARD MONUMENT MARKED E-13, P.S. NO. 9433
 ACCEPTED AS BEST AVAILABLE POSITON OF THE ACCEPTED POSITION OF THE CORNER.

- WITNESSES:
 N60°E 39.95' - NAIL & TAG IN 10" MAPLE (OBT)
 N53°W 69.95' - NAIL & TAG IN 8" TWIN RED OAK
 N80°W 98.62' - NAIL & TAG IN 30" MAPLE
 S45°E 63.18' - NAIL & TAG IN 12" MAPLE



Signed by Paul B. Lapham Date 12-01-95
 Surveyor's Michigan License No. 9433