

**SURVEY & REMONUMENTATION COMMISSION**  
**APR 29 1996**

**REMONUMENTATION CORNER  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in ISABELLA (County) Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey	T	<u>16N</u>	R	<u>5W</u>	<u>1-6</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
 COUNTY OF ISABELLA  
 RECEIVED FOR RECORD  
 DEC 11 10 38 AM '95  
 000079  
 SHARON A. BROWN  
 REGISTER OF DEEDS  
 Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, PAUL B. LAPHAM, in a field survey on OCTOBER, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
- |   |  |
|---|--|
| 1837 NICHOLSON, G.L.O.  | 10-19-73 LAPHAM, (132) 1-440<br>FOUND 1/2" IRON  |
| 1850 BURT, G.L.O. RESURVEY<br>SET POST                                      | WIT.-(3)S45°E, 39.45' 24" MAPLE<br>(5)EAST 32.55' FENCE CORNER<br>(6)S30°W 81.20' 4" ELM |
| WIT.-(1)HEMLOCK 26" N56°W 30<br>(2)HEMLOCK 30" S72°E 12                     |  |
| 1902 TRUSSELL, C.S.R. 3-179, C.S.R. 1-88<br>STONE "X" OLD RECOGNIZED CORNER | 11-05-73 LAPHAM, (L.C.R.C.) 156<br>SAME AS (132) 1-440                                   |
| WIT.-(3)SUGAR 4" S56°E 61<br>(4)PINE 36" S70°E 126 3/4                      |  |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 FOUND 1/2"x18" RE-ROD IN CENTER-LINE OF ASPHALT ROAD. FOUND TWO WITNESSES FROM 10-19-73 SURVEY

ACCEPTED BY THE ISABELLA COUNTY  
 REMONUMENTATION FEED GROUP  
 ON 2/2/95  
 William B. Ruddell, PS  
 County Representative

This Corner established in Isabella County Remonumentation Program.  
 See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- 1-6: 1/4 CORNER COMMON TO SECTIONS 14 & 15  
 SET 1/2"x24" STANDARD MONUMENT WITH CAP MARKED 1-6 P.S. NO. 9433  
 ACCEPTED AS BEST AVAILABLE EVIDENCE OF ACCEPTED POSITION OF THE CORNER.
- EAST 32.55' - NAIL & TAG IN CORNER POST (OBT)  
 N48°W 50.90' - NAIL & TAG IN 7" SCOTCH PINE  
 N85°W 40.48' - NAIL & TAG IN 8" SCOTCH PINE  
 S45°W 67.60' - NAIL & TAG IN 7" SCOTCH PINE



Signed by Paul B. Lapham Date 12-01-95  
 Surveyor's Michigan License No. 9433