

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>6</u> T. <u>1</u> S., R. <u>1</u> E.		<u>A-1, A-2, A-3</u>
2. PROPERTY CONTROLLING IN SECTION <u>6</u> T. <u>1</u> S., R. <u>1</u> E.		<u>A-1, A-2, A-3</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ S., R. _____ E.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, \_\_\_\_\_ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

A-1 Set corner  
 S61 1/2° E 20 LINKS 16" ELM N 42° E 18 LINKS 9" ELM

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- A-1 Found pointed stone set by Aaron Jackson in 1856. Replaced with 20' dia. concrete mon. with 2' dia. Brass Cap.
- A-2 Set 1" iron pipe with plastic cap on Meridian at a proportionate distance to East side of Section 6.
- A-3 Recovered with witnesses from Consumers Power Co. 5" dia. solid clay mon. set by Bean in 1873.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- A-1 20' dia. concrete mon. with 2' dia. Brass Cap.  
 S 78° E 31.16' clump 5 Maple S 00° 07' 36" W 50.0' concrete mon 12" dia, 18" high
- A-2 1" iron pipe with plastic cap  
 West 96.85' 12" Maple N 3° W 42.30' 5" maple  
 S 69° E 87.84' 6" Hickory East 74.91' 5" maple  
 West 66.00' 3/4" iron pipe  
 West 66.00' 3/4" iron pipe
- A-3 3" dia. solid clay mon.  
 N 39° E 6.48' 10" maple N 30° W S 21° E 20.62' 16" Twin White Ash  
 N 30° W 3.58' 20" Basswood

SIGNED BY \_\_\_\_\_ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

SIGNED BY \_\_\_\_\_ CHIEF OF SURVEY PARTY DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ MICHIGAN REGISTERED LAND SURVEYOR DATE \_\_\_\_\_ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_