

Note: - During Jan 1956 + Dec 1955 diligent search was made to locate any previously established meand. corner. Jackson Co. Surveyor Fred Riley had no data on any monuments.

So - We extended the Twp. Line N. from $\frac{1}{4}$ cor. the meted distance (apply the proration bet. $\frac{1}{4}$ & S.C.) to the N.C. ON Jan 19, 1956 set 4" cedar post, 9' long in ditch at 1892.18' N. of $\frac{1}{4}$ cor. Post has \square top with vert. spike in top for exact point.

W.L.P.

SEE JACKSON Co
MISC # 6

