

**JACKSON COUNTY
APPROVED LAND CORNER
P.A. 345 of 1990**

Chairman David C. Gulabinski
Date Nov. 12, 1997

WEST 1/4 POST, SECTION 19, HENRIETTA TOWNSHIP

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

#2052870
Liber 1555 Page 3
Page 1 of 1
Jackson Co., MI
Recorded
11/12/1997 10:57A
Mindy Reilly
Register of Deeds

For corners in
Jackson

(County)	Located In:	Corner Code #
1. Public Land Survey	T 1S R 1E	A-8
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

PS. 384

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Alan L. Scheppelman, in a field survey on October 30, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
POINT NOT SET IN ORIGINAL GOVERNMENT SURVEYS.

**SURVEY &
REMONUMENTATION**

APR 07 1998

SECTION

NOTES PROVIDED BY DAVID ERICKSON, PS 29245 SHOW A FOUND STONE. THIS INFORMATION IS FROM MARK FAUSER. DAVID ERICKSON STATED THAT ACCORDING TO MARK FAUSER THIS CORNER FIT OCCUPATION WITHIN THE SECTION VERY WELL.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND STONE 2' SOUTH OF RAILROAD TIE FENCE CORNER. THE FENCE IS ON THE EAST SIDE OF A NORTH-SOUTH DRAIN AND THE FENCE RUNS NORTH, EAST, AND WEST. THE AMENDED POSITION IS 6.87' WEST OF THE STONE AND IN THE CENTER OF THE DRAIN. ACCEPTED THE STONE AND FENCE AS THE BEST EVIDENCE OF THE CORNER. SET A 1" X 60" ALUMINUM PIPE IN THE DRAIN.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET A 1" X 60" ALUMINUM PIPE WITH ALUMINUM CAP STAMPED "A-8 T1S R1E LS 35998".
 N87°E SET NAIL & TAG 35998 IN THE SOUTH SIDE OF RR TIE POST 15.07'
 EAST STONE 6.87'
 S16°W SET NAIL & TAG 35998 IN THE WEST SIDE OF 14" MAPLE 75.51'
 S66°W SET NAIL & TAG 35998 IN THE NORTH SIDE OF 54" OAK 232.65'
 N83°W SET NAIL & TAG 35998 IN THE SOUTH SIDE OF 15" OAK 211.00'
 WEST SURVEY MARKER SIGN POST 12.0'



Signed by Alan L. Scheppelman Date 11/11/97
Surveyor's Michigan License No. 35998