

SURVEY & REMONUMENTATION

MAY 03 1995

WEST 1/4 POST, SECTION 30, HENRIETTA TOWNSHIP

LIBER 1450 PAGE 564

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

<u>Jackson</u> (County)	Located In:	Corner Code --#
1. Public Land Survey	T <u>1S</u> R <u>1E</u>	<u>A-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
 JACKSON COUNTY
 RECORDED

27 DEC 94 12:11 P.M.

GERALD J. McDEVITT
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Alan L. Scheppelman in a field survey on December 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

POINT NOT SET IN ORIGINAL GOVERNMENT SURVEY.

RICHARD GUTEKUNST JAN. 12, 1973	LCRC, L. 2, P. 35 FOUND POINTED STONE AT INTERSECTION OF FENCES N, S, & E. SET IRON ON SOUTH SIDE OF STONE.
	N75°W 30" OAK 86.39'; S40°E 12" OAK 21.70'
	N5°E 15" OAK 32.80'; S10°E 8" OAK 25.25'
	N45°E 12" OAK 9.60'; N80°E 18" HICKORY 38.60'
	EAST 10" HICKORY 24.85'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

APPROVED LAND CORNER
 P.A. 345 of 1996

Chairman Dean [Signature]
 Date Dec 8, 1994

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


FOUND POINTED STONE AND ALL WITNESSES (20d NAILS) EXCEPT THE 30" OAK TO THE NW WAS DEAD AND FALLEN. ACCEPTED THE STONE AS THE CORNER AND SET A STANDARD JACKSON COUNTY REMONUMENTATION MONUMENT 2.80' TO THE WEST ON THE RANGE LINE. I DID NOT DISTURB THE STONE OR IRON THAT WAS FOUND AT THE INTERSECTION OF THE FENCES.

\$ 2.00 REMONUMENTATION
 \$ 7.00 CORNER REMONUMENTATION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

4" x 36" CONCRETE MONUMENT WITH A JACKSON COUNTY REMONUMENTATION CAP STAMPED LS35998, FLUSH WITH GROUND.

EAST	POINTED STONE WITH 3/4" PINCHED PIPE ON THE SOUTH SIDE AT INTERSECTION OF FENCES N-S-E	2.80'
N10°E	FOUND NAIL IN SE SIDE OF 26" OAK	33.36'
N60°E	RESET NAIL OVER FOUND NAIL IN NW SIDE OF 15" OAK	11.69'
N80°E	FOUND NAIL IN N. SIDE OF 24" HICKORY	41.35'
N89°E	FOUND NAIL IN N. SIDE OF 12" HICKORY	27.55'
S40°E	FOUND NAIL IN E. SIDE OF 14" OAK	23.34'
S10°E	FOUND NAIL IN W. SIDE OF 10" OAK	25.75'



Signed by [Signature] Date 12/01/94

Surveyor's Michigan License No. 35998