

**JACKSON COUNTY
APPROVED LAND CORNER
P.A. 345 of 1990**

LIBER 1450 PAGE 711

Chairman Dean R. [Signature] SW Corner, Section 26, Henrietta Township
LAND CORNER RECORDATION CERTIFICATE
 Date Nov. 22, 1994 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in	Located In:	Corner Code #
<u>JACKSON</u> (County)		
1. Public Land Survey	T <u>1S</u> R <u>1E</u>	<u>I-11</u>
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____ Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
 JACKSON COUNTY
 RECORDED
 28 DEC 94 9:43 A.M.
 GERALD J. McDEVITT
 REGISTER OF DEEDS

**SURVEY &
 REMONUMENTATION**
 MAY 03 1995
COMMISSION

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David E. Erickson, in a field survey on October 11, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration

Post set in original government survey by J. Wampler, Deputy Surveyor, in November of 1825. No Bearing trees or witnesses recorded. In 1888, H.F. Bean reported "Post gone. Old ditch 80.00 South of N. Corner 29.41 N.W. creek and 16.57 East to River. Set F.C. post and stake N. Side of ditch." No witness trees near. Field notes dated 9-24-29 of Book H-2, Pages 10&11 (at Gutekunst survey office) indicate the distance East to "J-11" as 2664.0' and North to I-10 as 2639.8'. In 1988 D.A. Ankrom, L.S. #21265, recorded the corner as a "Fireclay with 1" pipe alongside" in Liber 4, Page 92.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3" x 24" Fireclay, 1.7' below surface of soybean field. A 3/4" (inside diameter) Iron pipe (length unknown) found on north side of fireclay. Also found pieces of tile around fireclay. Pipe left in place, too long to remove. Accepted fireclay as a careful and faithful perpetuation of the position of the original corner. Set a standard Jackson County Survey Monument (JCSM) in exact location of found fireclay. Top of monument is 1.7' below surface. Buried fireclay horizontally on east side of monument.

\$ 2.00 REMONUMENTATION
 \$ 7.00 CORNER REMONUMENTATION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set 4" dia. x 36" concrete monument with 1/2" x 36" rebar and Jackson County Standard Aluminum Cap stamped L.S. 29245, 1994, I-11

S66°W	Set spike/tag "29245" in South side of 14" Cottonwood	643.11'
S85°W	Set spike/tag "29245" in North side of 11" Cottonwood	576.74'
N63°W	Set spike/tag "29245" in South side of 17" Cottonwood	615.90'
N80°E	Set spike in East track of trail road	456.50'
S83°E	Set spike/tag "29245" in North side of twin 12" and 18" Cottonwood	479.97'
S55°E	Set spike/tag "29245" in North side of lone 40" cottonwood	676.45'
West	County Surveyor sign post	0.5'

Note: Bearings are magnetic

Signed by David E. Erickson
 Surveyor's Michigan License No. 29245

Date 12-7-94

