

JACKSON COUNTY
APPROVED LAND CORNER
P.A. 343 of 1998
ACTIVE
Chairman
Timothy B. DeWitt
Date 06-13-97

NORTHWEST CORNER, SECTION 1
HENRIETTA TOWNSHIP

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

#2044414
 Liber 1549 Page 134
 Page 1 of 1
 Jackson Co., MI
 Recorded
 08/15/97 10:56A
 Mindy Reilly
 Register of Deeds

For corners in
JACKSON
 (County)

Located in: _____ Corner Code # _____

Public Land Survey T 1 S R 1 E K-1

Property Controlling in Section S _____ T _____ R _____

Miscellaneous S _____ T _____ R _____

Property in Sec. S _____ T _____ R _____

SURVEY & REMONUMENTATION
APR 07 1998
SECTION
Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
 Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

DEAN R. GUTEKUNST in a field survey on July 15, 1996 & August 8 97

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as pressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

Original Government Post set by Joseph Wampler, Deputy Surveyor, October 1825.
 W. Oak 22" S 25 E 191 links (12.54') 90, Intersect Town on Base line
 W. Oak 12" S 80 W 80 links (52.80')
Perpetuation by H. F. Bean, 1888. Stone post has been kept.
 Maple 12" S 11 3/4 E 288 1/2 links (190.41')
 Hickory 8" N 79 E 241 1/2 links (159.39')

Not recorded in P. A. - 74.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found bottom 11" of a Fireclay, with 6" mid section above. Top of fireclay was missing.
 Found broken brick around bottom of fireclay.
 Corner was approximately on center line of Base Line Road (gravel) and approximately 3' West of center line of Fitchburg Road (blacktop) running South.
 Road was relocated Southerly, at intersection, when paved, and corner is now 9'± North of blacktop.
 Accepted Fireclay as a careful and faithful perpetuation of the position of the original corner as remonumented by Bean in 1888.

Set a Standard Jackson County Monument to replace the fireclay and left fireclay buried on the North side.

NOTE: The Ingham County line has not been remonumented at this point.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1 T1S, R1E Corner is a 4" diameter X 36" concrete monument with a 1/2" X 36" steel rod and an aluminum cap stamped LS 18658, which is a standard monument for Jackson County.

N 60° W Utility Pole 188.38' Pole barn spike and washer on Northeast side.
 N 65° E Utility Pole 232.26' Pole barn spike and washer on South side.
 S 35° E Southwest corner of a small frame shed 180.70'
 N 75° E center line of a metal Bell box 78.1'
 North Steel post and survey marker sign attached 2'

Recorded by Dean R. Gutekunst Date August 1, 1997
 Surveyor's Michigan License No. 18658



Record 314